BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

NAME OF THE WORK:-Providing Drinking water through borewells in Ward no. 06 Thanisandra.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	9	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc	Each BW	1938.46	Rupees One Thousand Nine Hundred Thirty Eight and Forty Six Paise Only
2	450.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc 0 to 50 m	Rmtr	315.18	Rupees Three Hundred Fifteen and Eighteen Paise Only
3	450.00	50 to 100 m	Rmtr	412.00	Rupees Four Hundred Twelve Only
4	450.00	100 to 150 m	Rmtr	458.35	Rupees Four Hundred Fifty Eight and Thirty Five Paise Only
5	450.00	150 to 200 m	Rmtr	484.10	Rupees Four Hundred Eighty Four and Ten Paise Only
6	450.00	200 to 250 m	Rmtr	560.32	Rupees Five Hundred Sixty and Thirty Two Paise Only
7	450.00	250 to 300 m	Rmtr	600.49	Rupees Six Hundred and Forty Nine Paise Only
8	450.00	300 to 350 m	Rmtr	622.00	Rupees Six Hundred Twenty Two Only
9	630.00	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/1993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes)	Rmtr	1364.75	Rupees One Thousand Three Hundred Sixty Four and Seventy Five Paise Only
10	90.00	Providing and fixing 250mm dia PVC pipe and as per specification and directions.	Rmtr	1133.00	Rupees One Thousand One Hundred Thirty Three Only
11	9	175 mm dia M.S. Casing cap	Each	103.00	Rupees One Hundred Three Only

No corrections Nil

21/12
E.E. (BTP. DIV)
21/12

	Quantity.	Description	Unit	Rates	
				In Figures	In Words
12	81	M.S. Casing pipe collars 'C' Class	Each	154.50	Rupees One Hundred Fifty Four and Fifty Paise Only
13	9	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 15.000 HP 25 stage (P.NO-XXXXIII, I.NO-33, PWD SR 16-17)	No	71020.00	Rupees Seventy One Thousand Twenty Only
14	4	For Additional Motor 15 HP 30 Stage	No	71020.00	Rupees Seventy One Thousand Twenty Only
15	2925.00	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings)b50mm dia GI pipe	Rmtr	340.26	Rupees Three Hundred Forty and Twenty Six Paise Only
16	1100.00	For Additional Motor GI Pipes	Rmtr	340.26	Rupees Three Hundred Forty and Twenty Six Paise Only
17	450.00	Providing & fixing heavy duty collar	Each	159.00	Rupees One Hundred Fifty Nine Only
18	180.00	For Additional GI Heavy Duty collar	Each	159.00	Rupees One Hundred Fifty Nine Only
19	5670.00	Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia	Mtr	164.29	Rupees One Hundred Sixty Four and Twenty Nine Paise Only
20	3000.00	For Additional PVC Cable	Mtr	164.29	Rupees One Hundred Sixty Four and Twenty Nine Paise Only
21	9.00	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	No.	14800.00	Rupees Fourteen Thousand Eight Hundred Only
22	4.00	For Additional Panel Board	No.	14800.00	Rupees Fourteen Thousand Eight Hundred Only
23	198000.00	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm	Sqm	0.34	and Thirty Four Paise Only
24	88000.00	Additional MS Box	Sqm	0.34	and Thirty Four Paise Only

No of corrections -Nil

E.E. (BTP. DIV) 21/12

21/12

	Quantity.	Description	Unit	Rates	
				In Figures	In Words
25	9.00	Providing & Fixing of clamps set and borewell cap to the pump (MR)	No's	690.00	Rupees Six Hundred Ninety Only
26	27.00	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. (PWD SR 16-17, P.NO.XXIII, Sl.no, 659)	No's	1282.60	Rupees One Thousand Two Hundred Eighty Two and Sixty Paise Only
27	27.00	Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline. 50mm dia (PWD SR 16-17, P.NO.XXIV, Sl.no, 673)	No's	1749.00	Rupees One Thousand Seven Hundred Forty Nine Only
28	27.00	Providing and fixing of 50mm GI bend to motor GI FITTINGS TABLE)	No's	232.14	Rupees Two Hundred Thirty Two and Fourteen Paise Only
29	27.00	Providing and fixing of 50mm GI Nipple to motor GI FITTINGS TABLE)	No's	110.56	Rupees One Hundred Ten and Fifty Six Paise Only
30	27.00	Providing and fixing of 50mm GI union to the motor (GI FITTINGS TABLE)	No's	237.12	Rupees Two Hundred Thirty Seven and Twelve Paise Only
31	9.00	Labour Charges for end connection (MR)	No's	400.00	Rupees Four Hundred Only
32	405.00	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m)	Per length	90.64	Rupees Ninety and Sixty Four Paise Only
33	9.00	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc,. Complete for basement out door type. (MR)	No's	475.00	Rupees Four Hundred Seventy Five Only
34	9.00	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP	No's	906.40	Rupees Nine Hundred Six and Forty Paise Only
35	50.00	Additional MCB		906.40	Rupees Nine Hundred Six and Forty Paise Only
36	327.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... 63 Amps	No.	150.00	Rupees One Hundred Fifty Only
37	315.00	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554)	Mtr	169.95	Rupees One Hundred Sixty Nine and Ninety Five Paise Only
38	120.00	For Additional LTUG Cable	Mtr	169.95	Rupees One Hundred Sixty Nine and Ninety Five Paise Only
39	315.00	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces	Mtr	56.65	Rupees Fifty Six and Sixty Five Paise Only
40	120.00	For Additional	Mtr	56.65	Rupees Fifty Six and Sixty Five Paise Only
41	27.00	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm	Mtr	294.58	Rupees Two Hundred Ninety Four and Fifty Eight Paise Only
42	9.00	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia	No's	1699.50	Rupees One Thousand Six Hundred Ninety Nine and Fifty Paise Only

No of corrections -Nil

21/12

E.E. (STP DIV)

	Quantity.	Description	Unit	Rates	
				In Figures	In Words
43	9.00	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc,	No's	271.92	Rupees Two Hundred Seventy One and Ninety Two Paise Only
44	9.00	Supplying shunt capacitor's confirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating No's. (MR)	No's	1350.00	Rupees One Thousand Three Hundred Fifty Only
45	27.00	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc,. Complete. 50mm dia	No's	1515.80	Rupees One Thousand Five Hundred Fifteen and Eighty Paise Only
46	9.00	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches	No's	311.58	Rupees Three Hundred Eleven and Fifty Eight Paise Only
47	1624.50	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications	Cum	223.66	Rupees Two Hundred Twenty Three and Sixty Six Paise Only
48	3610.00	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 16-17)	Mtr	368.88	Rupees Three Hundred Sixty Eight and Eighty Eight Paise Only
49	1624.50	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications	Cum	59.36	Rupees Fifty Nine and Thirty Six Paise Only

No of corrections - Nil

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

21/12

21/12

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Appoved"

Chief Engineer
Yelahanka Zone
Bangalore Mahanagara
Palike

27/12/17